

ARMY INSTITUTE OF MANAGEMENT & TECHNOLOGY (AIMT)

Plot No M-1, Pocket P-5 Greater Noida (UP) 201315

TENDER NOTICE

Invites sealed tenders from experienced and reputed agencies for purchase and installation firefighting equipment

Tender form and other details can be downloaded from our website www.aimt.ac.in for any query please contact: Mob **8920177636/0120-2343503**

Last Date for Submission of Filled Tenders Alongwith A Demand Draft of Rs 500/- in favour of Army institute of Management & Technology payable at Greater Noida: 04:00 PM on 24 Feb 23

LIST OF ITEMS

S. NO.	DESCRIPTION	UNIT	QTY.	Rates	Amount	Total amount with GST
1.00	Supply, Installation, Testing & Commissioning of Heavy class MS Pipe including MS Elbow & Reducer. (MAKE : JINDAL HISSAR)					
a).	25 mm Dia	Mtr.	1			
b).	100 mm Dia	Mtr.	1			
2.00	Supply & Laying of Primer and paint of MS pipe 25 mm dia to 150 mm dia (1 quote primer and 1 quote paint). (MAKE: BERGER)	Mtr.	1			
3.00	Supply & Installation, Testing and Commissioning of Butter Fly Valve (PN 16) 100 mm dia including MS Flange, Nut, Bolt & Washer complete in all respect. (MAKE: ZOLOTO)	Nos	1			
4.00	Supply, Installation, Testing and Commissioning of Non-Return Valve 100 mm dia including MS Flange, Nut, Bolt & Washer complete in all respect. (MAKE: ZOLOTO)	Nos	1			
5.00	Supply, Installation, Testing and Commissioning of Ball Valve 25 mm dia including Nipple, Dhaga & Safeda complete in all respect. (MAKE: ZOLOTO)	Nos	1			
6.00	Supply, Installation, Testing & Commissioning of Hose reel Drum with 20 mm dia thermoplastic pipe & shut off nozzle including fastner, Union & Nipple complete in all respect work. (MAKE: NEWAGE)	Nos	1			
7.00	Supply, Installation, Testing and Commissioning of 100 mm dial SS Glycerin filled Pressure Gauge Including Isolation Cock complete in all respect. (MAKE : H-GURU)	Nos	1			

8.00	Supply, Installation, Testing and Commissioning of Pressure Switch including Isolation Cock & automation of pump. (MAKE : DANFOSS)	Nos	1			
9.00	Supply & Installation of Fire Brigade Inlet Connection Two Way. (MAKE:NEWAGE)	Nos	1			
10.00	Supply & Installation, Testing and Commissioning of Terrace Pump with C.I Body, Bronze Impeller, SS Shaft LPM 450, Head - 35 Mtr. 7.5 H.P, 9 Kw. This pump will include base frame and 4 AVM Pads with RCC Foundation. (MAKE : KIRLOSKAR)	Nos	1			
11.00	Supply & Installation, Testing and Commissioning of Terrace Fire Pump Panel . (MAKE:SHIVAM CONTROL PANEL)	Nos	1			
12.00	Supply & Installation, Testing and Commissioning of Air Release 25 mm dia. (MAKE:ZOLOTO)	Nos	1			
13.00	Supply & Installation, Testing and Commissioning of PVC Water Storage Tank 5000 ltr. Capacity with RCC Foundation. (MAKE:SINTEX/PLASTO/SUPREME)	Nos	1			
14.00	Supply & Installation, Testing and Commissioning of Overhead Tank Connector set with nipples, socket & unions and other required accessories.	Nos	1			
15.00	Supply & Installation, Testing and Commissioning of Copper cable 3 x 4 sqmm for pump & panel connection with required accessories. (MAKE:HAVELLS)	Mtr.	1			
16.00	RCC Core Cutting in Slab for MS Pipe.	Nos	1			
17.00	Supply & Installation and Commissioning of MS Angle Support including fastener, U clamp, Red Oxide Primer & PO Red Paint.	Kg	1			
18.00	Supply & Installation, Testing and Commissioning of Advance Micro Processor based Conventional Fire Alarm Panel 4-Zone with 12V battery. (MAKE-ASES Security)	Nos	1			
19.00	Supply & Installation, Testing and Commissioning of Hooter. (MAKE-ASES Security)	Nos	1			
20.00	Supply & Installation of MCP resetable type with transparent flip cover for protection. (MAKE-ASES Security)	Nos	1			
21.00	Supply & Installation, Testing and Commissioning of 2 x1.5 Sqmm FRLS Armoured Cable with cable tie, gitti & screw. (MAKE:Havells/Polycab)	Mtr.	1			
22.00	Supply & Installation and Commissioning of "EXIT" Signage 12 x 8 inches self-glow type.	Nos	1			